



Town of Greenville
P.O. BOX 60
GREENVILLE, WI 54942
PHONE (920) 757-5151 · FAX (920) 757- 0543
www.townofgreenville.com

Required Inspections

The following inspections are required for each project if that work is part of the total project.

- 1. Erosion**
Inspection to be made prior to disturbing soil and throughout construction.
- 2. Plumbing Sewer and Water Laterals**
Inspection to be made prior to closing the trench. Sewer line must be tested in the presence of the Inspector.
- 3. Footings**
Inspection to be made prior to pouring of concrete
- 4. Foundation Tile and Stone**
Inspection to be made after stone and drain tile are in place and prior to backfilling
- 5. Electric Service**
Inspection to be made after outside pedestal and inside panel are installed. Must have GFI protected outlet and inside panel protected from weather.
- 6. Underground Plumbing**
Inspection to be made prior to pouring the basement floor.
- 7. Framing**
Inspection to be made prior to installation of insulation or closing of walls.
- 8. Electric Rough-In**
Inspection to be made prior to installation of insulation or closing of walls.
- 9. Plumbing Rough-In**
Inspection to be made prior to closing of walls.
- 10. Heating Rough-In**
Inspection to be made prior to finished walls and ceiling being installed.
- 11. Insulation**
Inspection to be made prior to finished walls and ceiling being installed.
- 12. Final Inspection (Occupancy)**
Inspection to be made prior to occupancy of the structure (or portion thereof) for which the permits were obtained. This inspection will cover all trades for which permits were issued.

PLEASE NOTE: It is the responsibility of the Contactor of the trade involved to contact the Inspection Department for the required inspection. The Inspector will respond as soon as possible (the Municipal Code requires that be within 48 hours). However, it is requested that as much advance notice as possible be given so that the inspection can be scheduled in an orderly fashion.